

**CORNER RECORD (SEARCH)**

(Ref. FSM 5151.4)

Tract or  
Survey No.

Tower Unit


Cor.  
No. **AP-213**

T. 6 S. R. 34 E.  
Merid. Willamette

R.D. North Fork John Day  
N.F. Umatilla

County Umatilla  
State Oregon

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

Found a 5/8" rebar with 3 1/4" aluminum cap, projecting 5" out of the ground.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

6" Lodgepole Pine Snag, N. 85 1/2 E., 7.9 feet, with burnt out double blaze.  
9" Subalpine Fir Snag, N. 49 W., 4.5 feet, with scribing visible on burnt double blaze.

**PHOTO IDENTIFICATION DATA**

Photo No.  
Filed At.  
Object Ident.  
Ident. By  
Signature

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

From the jct. Of roads 5226 and 5226-200 walk westerly on 5226-200 approx. 0.15 miles to a switchback. The corner is located 100 feet west of the center of the switchback.

**PLANE COORDINATE POSITION DATA**

State: Zone:  
X:  
Y:  
Datum:

Signature  
**D. Schlaich**

Title  
**Land Surveyor**

Division

Headquarters  
**S.O.**

Date  
**10/27/1997**

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

8" Lodgepole Pine, S. 67 1/2 W., 116.2 feet, scribed "WB/214" "BT" on double blaze.

9" Lodgepole Pine, N. 83 W., 94.1 feet, scribed "WB/213" "BT" on double blaze.

Work Done By D. Schlaich Title Land Surveyor Date 10/27/1997 State Registration No. or Agency \_\_\_\_\_

Certified Corner Record Prepared? Yes  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

## CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County UMATILLA

State OREGON


Tract or

Survey No. Tower Unit

Cor.

No. AP-213

## CORNER DIAGRAM

TOWER  
UNIT

## DESCRIBE CORNER MONUMENT FOUND

NONE

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

## PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

## DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of FS rds. 5226 and 5226-200 walk westerly on 5226-200 approx. 0.15 miles to a switchback. The corner is located 100 feet west of the center of switchback.

## PLANE COORDINATE POSITION

State: Oregon Zone: North

X: 2,498,788.02'

Y: 510,708.37'

Datum: NAD1927

*Signature*

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT  
5/8" by 36" rebar, with a 3 1/4" aluminum cap, 34" in the ground, marked "NFJD WILDERNESS TOWER UNIT AP-213  
RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE  
6" Lodgepole Pine, S. 89 1/2° E., 7.9 ft., mkd. "WB/213"BT" on double blaze.  
9" Grand Fir, N. 44 3/4° W., 4.5 ft., mkd. "WB/213"BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 09-1993

State Registration No.  
or Agency

Certified Cor. Record Prepared ? NO

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Cor.

AP-213