

Index  
File No.

## CORNER RECORD (SEARCH)


(Ref. FSM 5151.4)

Tract or  
Survey No.

Tower Unit

Cor.  
No. AP-214T. 6 S. R. 34 E.  
Merid. WillametteR.D. North Fork John Day  
N.F. UmatillaCounty Umatilla  
State Oregon

## CORNER DIAGRAM



## DESCRIBE CORNER MONUMENT FOUND

Found a 5/8" rebar with 3 1/4" aluminum cap, projecting 3" out of the ground.

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

11" Lodgepole Pine Snag, N. 40 E., 7.6 feet, with scribing visible on burnt double blaze.  
10" Lodgepole Pine Snag, West, 6.8 feet, with scribing visible on burnt double blaze.

## PHOTO IDENTIFICATION DATA

Photo No.  
Filed At.  
Object Ident.  
Ident. By

Signature

## DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. Of roads 5226 and 5226-200 walk westerly on 5226-200 approx. 0.15 miles to a switchback. The corner is located 100 feet west of the center of the switchback to AP-213. Then S. 16 W., 76.0 feet to the corner.

## PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/27/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

8" Lodgepole Pine, N. 71 W., 87.7 feet, scribed "WB/214" "BT" on double blaze.

9" Lodgepole Pine, N. 39 1/2 W., 108.5 feet scribed "WB/213" "BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 10/27/1997

State Registration No.  
or Agency \_\_\_\_\_

Certified Corner Record Prepared ?

Yes

No

Filed At \_\_\_\_\_

Date \_\_\_\_\_

REMARKS

Index  
File No.

T. 6 S. R. 34 E.  
Merid. WILLAMETTE


CORNER RECORD (SEARCH)  
(Ref. FSM 7151.4)

R.D. NFJD  
N.F. UMATILLA  
County UMATILLA  
State OREGON

Tract or  
Survey No. Tower Unit

Cor.  
No. AP-214

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:  
Filed At.:  
Object Ident.:  
Ident. By:  
*Signature*

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
From the jct. of FS rds. 5226 and 5226-200 walk westerly on 5226-200 approx. 0.15 miles to a switchback. Then 100 feet west of the switchback to AP-213. Then S. 16° W., 76.0 feet to the corner.

PLANE COORDINATE POSITION

State: Oregon Zone: North  
X: 2,498,769.04'  
Y: 510,634.80'  
Datum: NAD1927

*Signature*  
D. Schlaich

Title  
Land Surveyor

Division

Headquarters  
S.O.

Date  
09-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, 35" in the ground, marked "NFJD WILDERNESS TOWER UNIT AP-214 RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

10" Lodgepole Pine, N. 46° E., 7.6 ft., mkd. "WB/214"BT" on double blaze.

10" Lodgepole Pine, N. 85 1/4° W., 6.8 ft., mkd. "WB/214"BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 09-1993

State Registration No.  
or Agency

Certified Cor. Record Prepared? NO

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Cor.

AP-214