

USDA-FOREST SERVICE

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA


County UMATILLA

State OREGON

Tract or  
Survey No. Tower Unit

Cor.  
No. AP-424

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND  
NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND  
NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,500,669.11'

Y: 499,439.87'

Datum: NAD1927

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of FS rds. 52 and 5226 travel northerly on 5226 approx. 3.37 miles. Then walk northerly approx 200 feet to AP-410 set in the saddle of a spur ridge. Follow the posted boundary westerly along the top of the spur ridge approx. 1/2 mile to the corner.

*Signature*

D. Schlaich

*Title*

Land Surveyor

*Division*

*Headquarters*

S.O.

*Date*

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS TOWER UNIT AP-424 RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

9" Lodgepole Pine, N. 14° E., 19.5 ft., mkd. "WB/424"BT" on double blaze.

9" Lodgepole Pine, N. 37° E., 10.4 ft., mkd. "WB/424"BT" on double blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date 07-1993

State Registration No.  
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Cor.

AP-424