

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)Tract or
Survey No.

Tower Unit

Cor.
No. AP-496T. 6 S. R. 34 E.
Merid. WillametteR.D. North Fork John Day
N.F. UmatillaCounty Umatilla
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 3 1/4" aluminum cap, set flush with the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

9" Western Larch Snag, N. 72 1/2 E., 11.6 feet, with burnt out double blaze.
6" Lodgepole Pine Snag, N. 51 W., 21.7 feet, with scribing visible on double blaze.

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. Of road 52 and trail 3156 (Big Creek) hike up the trail approx. 1.1 miles to the corner which is located 100 feet northwesterly of the trail.

PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/23/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 23" in the ground, N. 32 1/2 E., 18.8 feet.
23" Western Larch, N. 25 1/2 W., 105.0 feet scribed "WB/496" "BT" on double blaze.

Work Done By D. Schlaich Title Land Surveyor Date 10/23/1997 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No.

T.

R.

M. Willamette

Tract or Survey No.

Tower Unit

Cor. AP-496

Index

File No.

T. 6 S. R. 34 E.
Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NOTH FORK JOHN DAY County UMATILLA
N.F. UMATILLA. State OREGON


Tract or

Survey No. TOWER UNIT

Cor.

No. AP-496

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of road 52 and trail 3156 (Big creek) hike up the trail approx 1.1 miles to the corner which is located northwest of the trail 100 feet.

PLANE COORDINATE POSITION

State: Oregon Zone: North

X: 2,493,293.90'

Y: 497,331.08'

Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07/1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set at a point 100 feet northwesterly of and perpendicular to the centerline of trail 3156, a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, mkd. "NFJD WILDERNESS TOWER UNIT AP-496 RLS 2308 1993"

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

6" Lodgepole Pine, N 50° W, 22.0 feet, mkd. "WB/496" "BT".

9" Western Larch, N 72° E, 11.6 feet, mkd. "WB/496" "BT".

The BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By D. Schlaich	Title Land Surveyor	Date 07/1993	State Registration No. or Agency
Certified Cor. Record Prepared ? NO	Filed At:		Date

REMARKS

Index File No.	T.	R.	M.	Tract or Survey No.	Cor.
	6 S.	34 E.	W.M.	TOWER UNIT	AP-496