

USDA-FOREST SERVICE

Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

Tract or
Survey No. **Tower Unit**


Cor.
No. **AP-542**

T. 6 S. R. 34 E.
Merid. Willamette

R.D. North Fork John Day
N.F. Umatilla

County Umatilla
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 3 1/4" aluminum cap, set flush with the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

6" Lodgepole Pine Snag, with charred scribes visible on double blaze, S. 54 W., 20.5 feet.
10" Lodgepole Pine Snag, with charred scribes visible on double blaze, N. 80 W., 21.4 feet.

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. Of road 52 and trail 3156 (Big Creek) hike up the trail approx. 850 feet to the corner which is located 100 feet northwesterly of the trail.

PLANE COORDINATE POSITION DATA

State: Zone:
X:
Y:
Datum:

Signature

D. Gaylord

Title

Land Surveyor

Division

Headquarters

S.O.

Date

05/08/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 36" iron rod, set 35" in the ground with 3/4 brass washer "PLS 1636" attached at ground level, bears N. 21 E., 60.8 feet.
11" Lodgepole Pine, S. 58 E., 128.7 feet scribed "WB/542" "BT" on double blaze.

Work Done By D. Gaylord Title Land Surveyor Date 05/08/1997 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index File No.

T.

R.

M. **Willamette**

Tract or Survey No.

Tower Unit

Cor. **AP-542**

Index

File No.

T. 6 S.

R. 34 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County UMATILLA

State OREGON


Tract or

Survey No. Tower Unit

Cor.

No. AP-542

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of Forest Trail 3056 with road 52 travel northeasterly on the trail for approx. 850 feet. The corner is located northwesterly of the trail at 100 feet.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,488,420.41'

Y: 496,328.17'

Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

08-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS TOWER UNIT AP-542 RLS2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

6" Lodgepole Pine, S. 53 3/4° E., 20.5 ft., mkd. "WB/542"BT" on double blaze.

11" Lodgepole Pine, N. 81 3/4° W., 21.2 ft., mkd. "WB/542"BT" on double blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date 08-1993

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.
Tower Unit

Cor.
AP-542