

USDA-FOREST SERVICE

Index

File No. **U-10.93**

T. **6 S.** R. **34 E.**

Merid. **Willamette**

CORNER RECORD (SEARCH)

(Ref. FSM 5151.4)

Tract or
Survey No.

Tower Unit

Cor.
No. **AP-584**

R.D. North Fork John Day

County Umatilla

N.F. Umatilla

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.

Filed At.

Object Ident.

Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the crossing of Winom creek on road 52 travel southerly on road 52 approximately 0.45 miles. Then walk easterly 200 feet to AP-585. From this point ascend following the wilderness boundary N. 89 ¼ W., 1390 feet to the corner.

PLANE COORDINATE POSITION DATA

State:

Zone:

X:

Y:

Datum:

Signature
D. Schlaich

Title
Land Surveyor

Division

Headquarters
S.O.

Date
09/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" by 30" aluminum pipe with a 3 1/4" aluminum cap, 24" in the ground stamped "NFJD WILDERNESS TOWER UNIT T6S R34E AP-584 S28 RLS 2308 1997".

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with red plastic cap stamped "UMATILLA N.F.", set 21" in the ground, S. 36-32 E., 95.15 feet. 19" Western Larch, S 41 3/4 W, 21.1 feet, scribed "WB/584" "BT" on double blaze.

Work Done By D. Schlaich Title Land Surveyor Date 09/1997 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: Umatilla County Surveyor's Office Date 11/1997

REMARKS