

CORNER RECORD (SEARCH)

(Ref. FSM 5151.4)

T. 6 S. R. 34 E.

R.D. North Fork John Day

County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 1 1/2" aluminum cap, projecting 1" out of the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

8" Western Larch Snag, S. 81 E., 20.4 feet, with burnt out double blaze.
 10" Western Larch Snag, N. 6 W., 21.5 feet, with burnt out double blaze.
 Center of 3' high boulder, N. 41 W., 17.5 feet, no marks.
 Center of 3' high boulder, N. 61 E., 27.4 feet, no marks.

PHOTO IDENTIFICATION DATA

Photo No.

Filed At.

Object Ident.
 Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the Winom creek crossing on road 52 travel southwesterly on road 52 approx. 0.45 miles to a spur ridge on the north side of the road. Ascend the spur ridge approx. 850 feet to the corner which is located on the high point of the spur ridge.

PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/28/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 36" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 31" in the ground, N. 13 1/2 E., 13.9 feet.
RM, 5/8" X 36" rebar with red plastic cap stamped "UMATILLA N.F.", set 31" in the ground, S. 69 1/2 E., 25.4 feet.

Work Done By D. Schlaich Title Land Surveyor Date 10/28/1997 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

USDA-FOREST SERVICE

Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)


Tract or
Survey No. Tower Unit

Cor.
No. AP-625

T. 6 S. R. 34 E.
Merid. WILAMETTE

R.D. NFJD County UMATILLA
N.F. UMATILLA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

5/8" rebar, with a 1 1/2" aluminum cap, projecting 1" out of the ground, marked "USDA-FS WB 625 1991 LS 1636".

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

11" Western Larch, N. 5° W., 21.5 ft., mkd. "WB/625""BT" on double blaze.
9" Western Larch, S. 81° E., 20.4 ft., mkd. "WB/625""BT" on double blaze.
Center of 3' high boulder, N. 41° W., 17.5 ft.
Center of 3' high boulder, N. 61° E., 27.4 ft.
Both BT's have 3/4" brass washer mkd. "PLS 1636" nailed next to "BT" scribing.

PHOTO IDENTIFICATION DATA

Photo No.:
Filed At.:
Object Ident.:
Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the Winom creek crossing on road 52 travel southwesterly on road 52 approx. 0.45 miles to spur ridge on the north side of the road. Ascend spur ridge approx. 850 feet to the corner which is located on a high point on the spur ridge.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2,481,046.62'
Y: 499,184.19'
Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

08-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Work Done By _____ Title _____ Date _____ State Registration No. or Agency _____

Certified Cor. Record Prepared? **NO** Filed At: _____ Date _____

REMARKS

Index File No. _____ T. **6 S.** R. **34 E.** M. **W.M.** Tract or Survey No. **Tower Unit** Cor. **AP-625**