

USDA-FOREST SERVICE
Index
File No.

T. 6 S. R. 34 E.
Merid. Willamette


CORNER RECORD (SEARCH)
(Ref. FSM 5151.4)

R.D. North Fork John Day
N.F. Umatilla

County Umatilla
State Oregon

Tract or Survey No. **North Fork John Dav Unit**
Cor. No. **AP-573**

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 3 1/4" aluminum cap, set flush with the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

7" Lodgepole Pine Snag, N. 72 E., 15.5 feet, with scribing visible on burnt double blaze.
7" Western Larch Snag, S. 19 1/2 E., 10.6 feet, with burnt out double blaze.

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner is located 200 feet southerly of Winom creek, approximately 5100 feet southwesterly down the creek from the bridge on road 5200-440.

PLANE COORDINATE POSITION DATA

State: _____ Zone: _____
X:
Y:
Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/22/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with red plastic cap stamped "UMATILLA N.F.", set 22" in the ground, S. 32 1/2 W., 16.2 feet.

RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 23" in the ground, N. 61 1/2 W., 20.9 feet.

Work Done By D. Schlaich Title Land Surveyor Date 10/22/1997 State Registration No. or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

CORNER DIAGRAM




PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,477,054.85'

Y: 494,800.08'

Datum: NAD1927

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County UMATILLA

State OREGON

Tract or

Survey No. NFJD Unit

Cor.

No. AP-573

DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner is located 200 feet southerly of Winom creek, approx. 5100 feet southwesterly down the creek from the bridge on road 5200-440.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT
5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS AP-573 RLS 2308 1993".

ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE
7" Lodgepole Pine, N. 81° E., 15.5 ft., mkd. "WB/573""BT" on double blaze.
7" Western Larch, S. 13° E., 10.9 ft., mkd. "WB/573"BT" on double blaze.
Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date **07-1993**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

NFJD Unit

Cor.

AP-573