

CORNER RECORD (SEARCH)

(Ref. FSM 5151.4)

R.D. North Fork John Day

N.F. Umatilla


County Umatilla

State Oregon

Tract or
Survey No.

Cor.
No.

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.

Filed At.

Object Ident.

Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the crossing of road 52 over Winom creek, travel southeasterly on road 52 approximately 0.22 miles. Then walk East approximately 1700 feet to the corner..

PLANE COORDINATE POSITION DATA

State:

Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09/1997

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" by 30" aluminum pipe, with a 3 1/4" aluminum cap, 27" in the ground.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 20" in the ground, N. 45-33 E., 19.67 feet.

RM, 5/8" X 24" rebar with red plastic cap stamped "UMATILLA N.F.", set 22" in the ground, S. 44-58 E., 23.93 feet.

12" Western Larch, S. 73 1/2 W., 84.5 feet, scribed "C1/4 S28" "BT" on double blaze.

14" Western Larch, N. 77 1/2 W., 77.6 feet, scribed "C1/4 S28" "BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 09/1997

State Registration No.
or Agency

Certified Corner Record Prepared ?

Yes

No

Filed At: Umatilla County Surveyor's Office

Date 11/1997

REMARKS

Index File No. T-11

6 S.

R. 34 E.

M. Willamette

Tract or Survey No.

Cor.