


CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.

Filed At.

Object Ident.

Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of roads 52 and 5200-527 walk up 5200-527 approximately 350 feet. Then northwesterly approximately 40 feet to the 1/4 corner of sections 28 and 33 which is located near the top of the cut bank. From this point walk North 1330 feet to the corner which is located on the east side of a spur ridge.

PLANE COORDINATE POSITION DATA

State:

Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" by 30" aluminum pipe, with a 3 1/4" aluminum cap, 23" in the ground.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with red plastic cap stamped "UMATILLA N.F.", set 21" in the ground, S. 25-35 W., 83.45 feet.  
15" Western Larch, N. 19 3/4 W., 106.6 feet, scribed "CS1/16 S28" "BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 09/1997

State Registration No.  
or Agency

Certified Corner Record Prepared ?

Yes

No

Filed At: Umatilla County Surveyor's Office

Date 11/1997

REMARKS