


History of original corner establishment:

Corner originally established by Frank W. Campbell on July 23, 1883 under contract No. 468, as follows:

Set a post for the section corner from which:

- A 6" Pine bears N30° E, 15 links (9.90 feet).
A 10" Pine bears S44° E, 36 links (23.76 feet).
A 8" Pine bears S55° W, 27 links (17.82 feet).
A 10" Pine bears N70° W, 26 links (17.16 feet).
Each tree was scribed per the surveying instructions.



Description of corner evidence found:

- A small mound of stones at the corner.
A 8" Lodgepole Pine snag with scribes "T6SR34ES27 BT" visible bears N69° W, 17.16 feet.
A 7" down Lodgepole Pine with scribes "T6SR34ES26 BT" visible. Root hole bears N34° E, 9.9 feet.
A 7" down Lodgepole Pine with scribes "T6SR34ES34 BT" visible. Broken stump bears S58° W, 17.82 feet. A down and decayed Lodgepole Pine with fragmentary scribes visible. Root hole bears S44° E, 23.8 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by reference to the original bearing trees, set a 2 1/2 inch by 30 inch aluminum pipe 26 inches into the ground with a 2 1/2 inch aluminum cap attached which is marked as shown in the diagram above. Build a mound of stones around pipe from which:

- A 11" Western Larch bears N18° 30' W, 28.1 feet scribed "T6SR34ES27 BT".
A 16" Western Larch bears S43° 15' W, 60.1 feet scribed "T6SR34ES34 BT".
A 13" Western Larch bears S74° E, 25.5 feet scribed "T6SR34ES35 BT".
A 10" Western Larch bears N85° 30' E, 44.8 feet scribed "T6SR34ES26 BT".

Each new bearing tree is scribed on double blazes, has a 3/4" brass washer marked "1636", nailed flush to the lower scribed face and has a 54-2 Bearing Tree sign nailed above the blaze and a 54-9 Land Survey Monument sign nailed to the back of the tree.

I hereby certify the above corner point was perpetuated as hereon described on June 21, 1993. Magnetic declination: 20° E.

NAD1983 Geographic Position (+ or - 2 to 6 meters):
Latitude: 45-00-41.465 N
Longitude: 118-35-44.164 W

Witnessed by: Trina Alden
Longitude: 118-35-44.164 W

Witnessed by: Trina Alden



Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
(COUNTY OFFICIAL) by (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 7-93
Rec'd By KR
No. 93-61-R
V-17