


History of original corner establishment:

Corner originally established by Frank W. Campbell on August 1, 1883, under contract No. 468, as follows:

Set a post for the section corner from which:

- A 10" Pine bears N50° E, 104 links (68.64 feet).
 - A 8" Pine bears S31° E, 130 links (85.80 feet).
 - A 9" Pine bears S55° W, 132 links (87.12 feet).
 - A 6" Pine bears N13° W, 75 links (49.50 feet).
- Each tree was scribed per the surveying instructions.



Description of corner evidence found:

A down and decayed Lodgepole Pine with illegible reverse scribes visible. Root hole bears N22°45'W, 49.5 feet.
 A down and decayed Lodgepole Pine with illegible scribes visible. Root hole bears N24° E, 68.64 feet.
 The original bearing trees to the south are gone.
 I can tell by the way these two tree remains have fallen to the ground that they are the original bearing trees north of the corner.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as determined by reference to the original bearing tree remains, at record distance, set a 2 1/2 inch by 30 inch aluminum pipe 30 inches into the ground with a 2 1/2 inch aluminum cap attached which is marked as shown in the diagram above. From which:

- A 9" Lodgepole Pine bears N20°30'E, 83.7 feet scribed "T6SR34ES29BT".
- A 7" Lodgepole Pine bears S31° E, 43.1 feet scribed "T6SR34ES32BT".
- A 8" Lodgepole Pine bears S84°30'W, 58.4 feet scribed "T6SR34ES31BT".
- A 8" Lodgepole Pine bears N44°W, 76.3 feet scribed "T6SR34ES30BT".

Each new bearing tree is scribed on double blazes, has a 3/4" brass washer, marked "1636", nailed flush to the lower scribed face and has a 54-3, Bearing Tree sign nailed above the blaze and a 54-9, Land Survey Monument sign nailed to the back of the tree:

I hereby certify the above corner point was perpetuated as hereon described on June 21, 1993. Magnetic declination: 20° E.

NAD1983 Geographic Position (+ or - 2 to 6 meters):
 Latitude 45-00-43.383 N
 Longitude 118-39-26.627 W

Witnessed by: Trina Alden

REGISTERED PROFESSIONAL LAND SURVEYOR

Dennis L. Gaylord

OREGON
JUL 14, 1978
DENNIS L. GAYLORD
 1636

EXPIRES 12/31/93

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date 7-93
 Rec'd By KR
 No. 92-41-B