

Index  
File No.

## CORNER RECORD (SEARCH)

(Ref. FSM 5151.4)

Tract or  
Survey No.

Tower Unit

Cor.  
No. AP-351T. 6 S. R. 35 E.  
Merid. WillametteR.D. North Fork John Day  
N.F. UmatillaCounty Umatilla  
State Oregon

## CORNER DIAGRAM



## DESCRIBE CORNER MONUMENT FOUND

Found a 5/8" rebar with 3 1/4" aluminum cap, projecting 1" out of the ground.

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

6" Lodgepole Pine Snag, N. 77 E., 12.3 feet, with scribing visible on double blaze.  
7" Lodgepole Pine Snag, S. 12 W., 5.9 feet, with scribing visible on double blaze.

## PHOTO IDENTIFICATION DATA

Photo No.  
Filed At.  
Object Ident.  
Ident. By

Signature

## DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. Of roads 52 and 5226 travel northerly on 5226 approx. 4.77 miles. The corner is located approx. 200 feet westerly of the road.

## PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/28/1997

FS-7100-52 (9/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

8" Lodgepole Pine, S. 39 1/2 W., 13.0 feet, scribed "WB/351" "BT" on double blaze.

6" Lodgepole Pine, N. 22 W., 19.6 feet scribed "WB/351" "BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 10/28/1997

State Registration No.  
or Agency

Certified Corner Record Prepared ?

Yes

No

Filed At:

Date

REMARKS

Index

File No.

T. 6 S. R. 35 E.

Merid. WILLAMETTE

CORNER DIAGRAM



TOWER  
UNIT AP-351

## PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

## PLANE COORDINATE POSITION DATA

State: Oregon Zone: North

X: 2,504,945.77'

Y: 502,866.93'

Datum: NAD1927

CORNER RECORD (SEARCH)  
(Ref. FSM 7151.4)Tract or  
Survey No. Tower UnitCor.  
No. AP-351

R.D. NFJD

County UMATILLA

N.F. UMATILLA

State OREGON

DESCRIBE CORNER MONUMENT FOUND  
NONEDESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND  
NONEDESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
From the jct. of FS rds. 52 and 5226 travel northerly on 5226 approx. 4.77 miles. The corner is located approx. 200 westerly of the road.*Signature*

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

06-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, 35" in the ground, marked "NFJD WILDERNESS TOWER UNIT AP-351 RLS2308 1993".

ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

7" Lodgepole Pine, S. 10° W., 5.9 ft., mkd. "WB/351"BT" on double blaze.

7" Lodgepole Pine, N. 77° E., 12.8 ft., mkd. "WB/351"BT" on double blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date **06-1993**

State Registration No.  
or Agency

Celified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

35 E.

M.

W.M.

Tract or Survey No.

Cor.

AP-351