


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

2-4

History of original corner establishment:

Corner not established during original survey.



Description of corner evidence found:

No evidence found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point determined by survey, we set a 2"x30" Galvanized Iron Pipe 20" in the ground and supported in a mound of stone 4' base to top of pipe, with brass cap attached, marked:

From which we mark the following bearing objects:

An "X B0" chiseled 8" above ground on a vertical rock face (5' high and 12' long) bears N58½°E 11.95 ft.


And an "X B0" chiseled 6" above ground on a vertical bedrock face (3' high and 3' wide) bears S27° E 33.05 ft.

Corner location established and perpetuated in accordance with Umatilla National Forest Cadastral Survey Contract No. 53-04R3-2-01275.

Magnetic Compass (Declination 18½° East)
Steel Tape

August 27, 1982

Witnesses: Gary Langlitz
Greg Orton
Jeff Anderson



REGISTERED PROFESSIONAL LAND SURVEYOR

Gary L. Langlitz

OREGON
JULY 22, 1977
GARY L. LANGLITZ
1099

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 1st day of January, 1983
David H. Klein by _____
(COUNTY OFFICIAL) (DEPUTY)

2-4

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 83-03-B