

USDA-FOREST SERVICE

INDEX

FILE NO. C-15 CORNER RECORD (SEARCH) Tract or  
 (Ref. FSM 7151.4) Survey No. \_\_\_\_\_ Cor. \_\_\_\_\_  
 T. 7 S R. 32 E R.D. North Fork John Day County Grant  
 Merid. Willamette N.F. UMATILLA State Oregon \_\_\_\_\_ 1

CORNER DIAGRAM

1 DESCRIBE CORNER MONUMENT FOUND  
 1 Found standard BLM brass cap stamped as shown in the diagram.  
 1 T7SR323E 1  
 N C1/4 S3 1  
 1 1968 1 ----- 2

1 DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

1 A 12" dbh Douglas Fir bears S84 1/4°E, 57.1' with healed blaze.  
 1 A dead 5" dbh Douglas Fir bears S50°W, 5.0' with visible scribe.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
 Filed at. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
 Signature \_\_\_\_\_

PLANE COORDINATE POSITION DATA

1 DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
 State \_\_\_\_\_ Zone \_\_\_\_\_ 1 Follow FSR 55 from Highway 395 to FSR 5505. Follow FSR 5505 2 miles. Cross a cattle guard  
 X \_\_\_\_\_ 1 and turn west after 100 yards. Follow this primitive road 1 mile around a steep hill and then  
 Y \_\_\_\_\_ 1 up a steep grade for 0.6 mile to a junction. Follow the south fork of the road 0.4 mile to a  
 Estab. By \_\_\_\_\_ 1 wood section line post. From this post, follow the posted line about 300' down a steep hill  
 Agency \_\_\_\_\_ 1 to the corner. ----- 4

Signature David L. Haddock Title Surveyor Division \_\_\_\_\_ Headquarters Pendleton, OR Date 2-15-84 FS-7100-52 (3/68) 5

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Cleared brush and debris away from corner.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Set new bearing trees.

A 7" dbh Douglas Fir bears N0 3/4°E, 24.8' scribed C1/4 S3 BT.

A 7" dbh Douglas Fir bears N28 1/4°E, 27.0' scribed C1/4 S3 BT.

A 18" dbh Douglas Fir bears S54°W, 23.8' scribed C1/4 S3 BT.

An aluminum washer stamped RLS 852 is nailed between the letters B and T on each new tree. BT and LSM signs are attached to each bearing tree. Six inch red bands are painted around each bearing tree and the blazes are painted red.

10

Work Done By David L. Haddock Title Land Surveyor Date 9-21-93 or Agency PLS 852 State Registration No.  
Certified Cor. Record Prepared? x Yes No Filed At: Grant County Surveyor Date: 10-93 11

REMARKS

12

Index File No. C-15 T. 7 S. R. 32 E. M. Willamette Tract or Surv. No. Cor. 13

Index  
 File No. C-15  
 T 7S R. 32E  
 Merid. W.M.

**CORNER RECORD (SEARCH)**

N. Fk. (Ref. FSM 7151.4)  
 R.D. John Day County Grant  
 N.F. Umatilla State Or.

Tract or Survey No. \_\_\_\_\_  
 Cor. No. \_\_\_\_\_

**CORNER DIAGRAM**



$C\frac{1}{4}$  S3

**DESCRIBE CORNER MONUMENT FOUND**

$2\frac{1}{2}$ " iron pipe with  $3\frac{1}{4}$ " brass cap (BLM) mkd.:

T7S R32E  
 $C\frac{1}{4}$  S3  
 1968

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

D. Fir, 12", S84 $\frac{1}{2}$ °E, 86 $\frac{1}{2}$  lks.; with healed blaze.  
 D. Fir, 6", S50°W, 7 $\frac{1}{2}$  lks.; scribing visible.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estob. By \_\_\_\_\_  
*Agency*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner falls on steep Wly slope, E. of cr. Posted line to W.

Signature

*FJ Munro*

Title  
 PLS

Division

Headquarters

Date

7/11/90

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

None..

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

None..

10

Work Done By. F.S. Munro Title PLS Date 7/7/90 State Registration No. or Agency 1832  
Certified Cor. Record Prepared ? Yes No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

11

REMARKS

12

Index File No. 0-15 T. 7S R. 32E M. W.M. Tract or Surv. No. \_\_\_\_\_ Cor. \_\_\_\_\_

13