

Index

File No.

T. 7 S. R. 34 E.  
Merid. WILLAMETTE

**CORNER RECORD (SEARCH)**  
(Ref. FSM 7151.4)

R.D. NOTH FORK JOHN DAY County GRANT  
N.F. UMATILLA State OREGON

Tract or  
Survey No. **NFJD UNIT**

Cor.  
No. **AP-1197**

**CORNER DIAGRAM**

AP-1197



**DESCRIBE CORNER MONUMENT FOUND**

NONE

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

NONE

**PHOTO IDENTIFICATION DATA**

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

*Signature*

**DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

From the jct of road 5225 and F.S. trail 3021 (Martin creek) go south on the trail approx 500 feet to corner which is located 100 feet west of the trail.

**PLANE COORDINATE POSITION**

State: Oregon Zone: North

X: 2,501,354.73'

Y: 478,008.45'

Datum: NAD1927

Signature

**D. Schlaich**

Title

**Land Surveyor**

Division

Headquarters

**S.O.**

Date

**10/1993**

FS-7100-52 (3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set at a point 200 feet easterly of and perpendicular to the centerline of road 5225 and 100 feet southerly of and perpendicular to the centerline of trail 3021, a 5/8" by 3/6" rebar, with a 3 1/4" aluminum cap, flush with the ground, mkd. "NFJD WILDERNESS AP-1197 RLS 2308 1993"

**ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

9" Englemann Spruce, S 87° E, 47.8 feet, mkd. "WB/1197" "BT".

10" Englemann Spruce, N 23° W, 42.7 feet, mkd. "WB/1197" "BT".

BT's are double blazed and have a 3/4" brass washer stamped "RLS 2308" nailed to the lower blaze by the "BT" scribing.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **10/1993**

State Registration No.  
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

**REMARKS**

Index File No.

T.

**7 S.**

R.

**34 E.**

M.

**W.M.**

Tract or Survey No.

**NFJD UNIT**

Cor.

**AP-1197**