

Index

File No. C.73-18

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. NFJD Unit

Cor.

No. AP-759

T. 7 S. R. 34 E.

R.D. NFJD


County GRANT

Merid. WILAMETTE

N.F. UMATILLA

State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE.

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5225 travel southeasterly on 5225 approx. 2.50 miles to a property line crossing. Then walk S. 0°33' E., approx. 500 feet to the corner.

PLANE COORDINATE POSITION

State:

Zone:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" by 28" aluminum pipe, with a 3 1/4" aluminum cap, 26" in the ground, marked "T7S R34E NFJD S2 AP-759 RLS 2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

7" Lodgepole Pine, N. 81° E., 6.3 ft., marked "WB/759""BT" on double blaze.

10" Lodgepole Pine, S. 45 1/2° E., 46.7 ft., marked "WB/759""BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to the "BT" scribing on the lower blaze.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **10-1993**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **YES**

Filed At: **Grant County Surveyor's Office**

Date

REMARKS

Index File No.
C.73-18

T.
7 S.

R.
34 E.

M.
W.M.

Tract or Survey No.
NFJD Unit

Cor.
AP-759