

Index

File No. D-18

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)Tract or
Survey No.

NFJD.

Cor.
No.

AP-760

T. 7 S. R. 34 E.

R.D. NFJD


County GRANT

Merid. WILLAMETTE

N.F. UMATILLA

State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 2 1/2" aluminum pipe, with a 2 1/2" aluminum cap, projecting 18" out of the ground, 6" above a rock mound 6" in diameter, marked "SW1/16 S2 RPLS 1910 1986".

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

8" Lodgepole Pine, S. 71° W., 17.9 ft., with scribing visible on double blaze.
Downed 6" Lodgepole Pine (record S. 68° E., 4.8 ft.) with scribing visible on double blaze.
Both BT's have a 3/4" brass washer stamped "RPLS 1910" nailed to the lower blaze.

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION DATA

State:

Zone:

Y:

Datum:

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of road 52 and 5225 travel southeasterly on 5225 for approx. 2.65 miles to the crossing of a East-West property line. Then walk West, approx. 400 feet to the corner.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

MARKED NEW BT:

9" Lodgepole Pine, S. 55 1/2° E., 11.2 ft., marked "SW1/16 S2""BT" on double blaze and nailed a 3/4" brass washer stamped "RLS 2308" next to the "BT" scribing on the lower blaze.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **10-1993**

State Registration No.
or Agency

Certified Cor. Record Prepared? **YES**

Filed At: **Grant County Surveyor's Office**

Date

REMARKS

Index File No.
D-18

T.
7 S.

R.
34 E.

M.
W.M.

Tract or Survey No.
NFSD UNIT

Cor.
AP-760