

Index

File No. **H.51-15**

T. 7 S. R. 35 E.

Merid. WILAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County GRANT

State OREGON


Tract or

Survey No. NFJD Unit

Cor.

No. AP-1396

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE.

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and Forest trail 3021 travel westerly on the trail approx. 1.7 miles to the property line crossing. Then walk S. 1° 27' E., approx. 100 feet to the corner.

PLANE COORDINATE POSITION

State:

Zone:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" by 28" aluminum pipe, with a 3 1/4" aluminum cap, 6" in the ground and flush with a rock mound 18" high, marked "T7S R35E NFJD S10 AP-1396 RLS 2308 1993".

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

44" Western Larch, N. 6° E., 35.3 ft., marked "WB/1396""BT" on double blaze.

10" Douglas Fir, N. 89° W., 27.8 ft., marked "WB/1396""BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to the "BT" scribing on the lower blaze.

Work Done By **D. Schlaich**

Title **Land Surveyor**

Date **10-1993**

State Registration No.
or Agency

Certified Cor. Record Prepared? **YES**

Filed At: **Grant County Surveyor's Office**

Date

REMARKS

Index File No.
H.51-15

T.

7 S.

R.

35 E.

M.

W.M.

Tract or Survey No.
NFJD Unit

Cor.
AP-1396