

Index

File No. **M-21.79**

T. 7 S. R. 35 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County GRANT

State OREGON


Tract or

Survey No. NFJD Unit

Cor.

No. AP-1485

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE.

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

PLANE COORDINATE POSITION

State:

Zone:

Y:

Datum:

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 51 and 52 travel northwesterly on 52 approx. 3.7 miles to the property line crossing. Then walk westerly, following the property line, approx. 1000 feet to the corner which lies in the center of Trout Creek.

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 5/8" by 36" rebar, with a 3 1/4" aluminum cap, 24" into the center of Trout creek, marked "T7S R35E NFJD AP-1485 S13 RLS 2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

7" Lodgepole Pine, S. 11 3/4° W., 100.6 ft., mkd. "WB/1485""BT" on double blaze, with a 3/4" brass washer stamped "RLS 2308" nailed next to the "BT" scribing on the lower blaze.

5/8" by 24" rebar, with 1 1/2" aluminum cap set 23" in the ground, N. 88°28' W., 87.05 ft., mkd. "USDA-FS S13 87.05 FT 2308".

Work Done By D. Schlaich

Title Land Surveyor

Date 10-1993

State Registration No.
or Agency

Certified Cor. Record Prepared ? YES

Filed At: Grant County Surveyor's Office

Date

REMARKS

Index File No.
M-21.79

T.

7 S.

R.

35 E.

M.

W.M.

Tract or Survey No.
NFJD Unit

Cor.

AP-1485