

## Oregon &amp; Washington Boundary Line.

all in deeply cut characters. Built a very durable mound of stone, 6 ft. sq. at base and tapering up  $4\frac{1}{2}$  ft. to post in center. Dug trench & pits, of usual size & position. Ascend steep side of ridge, which becomes rocky near the top; cross end of ridge, 10.39, intersected N. & S. line, bet. Rs. 32 & 33. Set post for Secs. 13-18, situated on S. face of stony mountain. Built mound of stones about post, properly marked. No trench or pits on account of rocky nature of location. Descending, cross ravine, proceed up and along flat top of ridge and thence over N.E. decline of ridge top, 40 chs. terminate in a hollow, bearing N.E. & S.W.

Bearings:

To large bolder, on hillside, N.48°05' E., dist. about 25 chs.

To S.W. bank of Walla Walla River, N.19°42'E., dist. 2 miles.

1/2 M. Made excavation,  $2\frac{1}{2}$  ft. deep; deposited charred stakes. Built mound, 6 ft. sq. & 3 ft. high. Dug trench & pits of the usual size. Post, 6 ft. long & 4 ins. sq.; trimmed; marked on W. face, deeply cut, " $\frac{1}{2}$  M."

1864

May 31 Ascend - 42, cross top of ridge; descend; cross rocky ravine; ascend to smaller ridge; cross & descend to bed of rocky ravine and end of 80 chs., course of ravine N.N.E. Could get no bearings. Made excavation, 3 ft. deep; deposited bones; planted a heavy post of prescribed size & marking. Erected a monument of large stones about post, a most durable monument. Ascending in 5 chs., cross small ridge and descend, 10 chs., intersected

12 M.

S 17-18 N. & S. line bet. Secs. 17-18. Set post in mound, with trench, pits, etc., as prescribed. Ascend foot of ridge to top and descend 20.50 to bottom of ravine; thence over gradual decline to N., enter circular flat, pointing N.E.; below hill and towards small ravine, end of 40 chs.

Bearings: