

## Green &amp; Washington Boundary Line

dinal points. Thence E.; ascend hill 6 chs. to top; cross fence and enter Been's claim; descend, 39 chs. edge of bluff, 40 chs. side of steep bluff, bearing N.W. & S.E. Could not set instrument for bearings. Made excavation deposited charred wood & bones. Planted an alder post 5½ ft. long & 5 ins. sq., marked on W. side "½ M". Erected mound of earth, 4 ft. sq. and 3 ft. high. Dug trench for 3 sides of mound, none for the lower or N. side, because the ground was too steep; also 3 pits. 30 lks. to ft. of bluff. Leaving this mound the Bdy. passes E. in 50 lks. reaches ft. of bluff and bottom land; thence 42.50 chs. to an alder tree, blazed & marked "W". 42.80 chs. S. edge of Cottonwood Creek. A mountain stream, 20 lks. wide, but shallow, coursing N.W.; and at this place has some few cottonwood & alder trees on its banks. Cross road bearing S.E. & N.W.; enter cultivated fields. 80 chs. terminate in Mr. Swasey's field, at intersection of line N. & S. bet. Rs. 36 & 37 E., Sec. line 13-18.

## Bearings:

35 M. To chimney of Mr. Foster's house, N.21°19'E., dist. 85 chs.  
Ridge of Catholic Seminary, N.48°21'W., dist. 7 miles.  
Ridge of Frank Sheldon's house, dist. 60 chs., S.61°03'E.  
Upper or SW. Cor. of ditch on bluff, S.47°42'W., dist. 50 chains.

Made excavation, 4 ft. deep; deposited cows head, a quantity of bones, some charred stakes & a glass bottle. Planted a heavy seasoned cottonwood post, 9½ ft. long & 15 ins. diam. Top beveled; sides trimmed & ground end charred. Marked in deeply cut characters on N. face "W", on S. "O", on E. "46° L 1864" and on W. "35 M". Mound, 8 ft. sq. and 4½ ft. high; earth well packed & planted with seed. Soil of 1st quality and under cultivation. This monument has been re-rendered as permanent as possible, because of proximity to the 1st Astronomical Station and also the intersection of the R. line,