

Base Line , Range 29 East.

Chains 40.00	Set post for qr. sec. cor. and built mound of Earth as per instructions.	
80.00	Set post for corner to sections 31 and 32 and built mound of Earth as per instructions. Land, broken. Soil, 2nd rate.	600
	West on South Boundary of sec. 31. Var. 16° 15' East.	
40.00	Set post for qr. sec. cor. with a stone 5 ins. square and 15 ins. long and built mound of Earth as per instructions.	
87.19	To corner established for Ranges 28 and 29 E. This measurement makes the line 7.19 chs. longer than it was reported. This I throw upon West of the Township. May 12, 1860.	
	Subdivisions of T. 1 N., R. 29 East. Surveyed by L F. Cartee under contract No. 88. Dated May 11, 1860.	
	North between sections 35 and 36.	
40.00	Set post for qr. sections cor. in mound of Earth as per instructions.	20
80.00	Set post for corner to sections 25, 26, 35 and 36 and built mound of Earth as per instructions. Land, sloping to the north. Soil, 2nd rate.	50
	East on random line between sections 25 and 36. Var. 21° East.	
40.00	Set temp. qr. sec. post.	
79.50	Intersected line at corner. West on true line between sections 25 and 36.	
39.75	Set post for qr. sections cor. and built mound of Earth as per instructions.	
79.50	Intersected line at corner. West on true line between sections 23 and 36.	