

Subdivisions of T. 1 N., R. 29 E.

Chains		
39.75	Set post for qr. section cor. and built mound of Earth as per instructions.	
79.50	To section corner. Level. Soil, 2nd rate, slopes to the North.	
	North between sections 25 and 26.	
40.00	Set post for qr. section corner and built mound of Earth as per instructions.	-50
80.00	Set post for corner to sections 23 and 24, 25 and 26, and built mound of Earth as per instructions. Land, gently rolling, slopes North. Soil, 2nd rate.	-50
	East on random line between secs. 24 and 25. Var. $18\frac{1}{2}^{\circ}$ East.	
40.00	Set temp. qr. sec. post.	
79.10	Intersect at sec. corner. Level. West, on true line, between secs. 24 and 25.	
39.55	Set post for qr. sec. cor. and built mound of Earth as per instructions.	
79.10	To section corner. Soil, 2nd rate. Land, gently rolling.	
	North between sections 23 and 24.	
40.00	Set post for qr. section corner and built mound of Earth as per instructions.	
80.00	Set post for corner to sections 13, 14, 23 and 24 and built mound of Earth as per instructions. Land, gently rolling. Soil, 2nd rate.	
	East, on random line between secs. 13 and 24. Var. $19^{\circ} 30'$ East.	
40.00	Set temp. qr. sec. post.	