

Baseline through Range 30 East
 Surveyed by David P. Thompson under contract No. 79.
 Dated July 26, 1858.

Chains	175th Mile East on South boundary of sec. 31. Var. 18° East.
40.00	Set stone 5 x 15 x 15 ins. for corner and build mound of Earth as per instructions.
70.70	Large Indian Trail bears N. and S.
80.00	Set post for corner to secs. 31 and 32 and build mound of Earth as per instructions. Land, level. Grass plains
	176th Mile East on South boundary of sec. 32. Var. 22° East.
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of Earth as per instructions.
80.00	Set a stone, 10 x 15 x 15 ins., for corner to secs. 32 and 33 and build a mound of Earth as per instructions. Land, level. Grass plains
	June 7, 1859.
	177th Mile East on South boundary of sec. 33. Var. 17° 40' East.
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 33 and 34 and build a mound of Earth as per instructions. Land, level. Grass plains Soil, 1st rate.
	178th Mile East on South boundary of sec. 34. Var. 20° East.
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of Earth as