

## Remeasurement of Base Line through 30 East.

Chains		
	<p>and raised mound as per instructions. Destroyed pre-established sec. cor.</p> <p>Land, first <math>\frac{1}{2}</math> mile nearly level, balance rolling.</p> <p>Soil, good, 2nd rate.</p>	
	<p>West on South boundary of sec. 35.</p> <p style="text-align: right;">Var. <math>20\frac{1}{4}^{\circ}</math> East.</p>	
3.00	To a hollow and ascend.	-50
40.00	Set qr. sec. post.	+50
	<p>Drove charred stake and built mound as per instructions.</p> <p>Destroyed pre-established qr. sec. cor.</p>	
80.00	Set post for cor. to secs. 34 and 35. Drove charred	
	<p>stake and built a mound as per instructions. Destroyed pre-established sec. cor.</p> <p>Land, rolling prairie.</p> <p>Soil, good, 2nd rate.</p>	
	<p>West on South boundary of sec. 34.</p> <p style="text-align: right;">Var. <math>20\frac{1}{4}^{\circ}</math> East.</p>	
40.00	Set qr. sec. post. Drove charred stake and built mound	
	<p>as per instructions. Destroyed pre-established qr. sec. cor.</p>	
80.00	Set a post for cor. to secs. 33 and 34. Drove charred	
	<p>stake and built mound with trench and pits as per instructions. Destroyed pre-established sec. cor.</p> <p>Land, nearly level prairie.</p> <p>Soil, good, 2 nd rate.</p>	
	<p>West on South boundary of sec. 33.</p> <p style="text-align: right;">Var. <math>21^{\circ}</math> East.</p>	
40.00	Set qr. sec. post. Drove charred stake and built mound	
	<p>with trench and pits as per instructions. Destroyed pre-established qr. sec. cor.</p>	
80.00	Set post for cor. to secs. 32 and 33. Drove charred	
	<p>stake and built mound with trench and pits as per instructions. Destroyed pre-established sec. corner.</p>	