

Subdivisions of T. 1 N., R. 30 E.

Chains	
	<p>mound of Earth; drove charred stake with trench and pits as per instructions. This line crosses several ridges and hollows sloping towards a large hollow on the W., running N.W.</p> <p>Land, rolling Prairie.</p> <p>Soil, 2nd rate.</p>
	<p>East on random line between secs. 25 and 36.</p> <p style="text-align: center;">Var. 22° 40' E.</p>
40.00	Set temporary quarter sec. post.
80.08	Intersect Guide Meridian 48 lks. S. Corner to secs. 25, 30, 37 and 36.
	S. 89° 40' W., on true line, between secs. 25 and 36.
40.04	Set post for quarter section corner and raised mound of Earth and drove charred stake as per instructions.
80.08	The post corner to secs. 25, 26, 35 and 36.
	Land, rolling prairie.
	Soil, good, 2nd rate.
	North between secs. 25 and 26.
40.00	Set a post for quarter sec. corner and raised mound of Earth and drove charred stake as per instructions.
43.00	Var. 23° E.
80.00	Set a post for corner to secs. 23, 24, 25 and 26 and raised mound of stone, drove a charred stake as per instructions. This line crosses several ridges and small hollows, course N. descending into big hollow before noted.
	Land, considerably rolling, stony in places.
	Soil, 2nd and 3rd rate.
	East on random line between secs. 24 and 25.
	Var. 22° E.
40.00	Set temporary quarter sec. post.
80.24	Intersect corner to 19, 30, 24 and 25 on Guide Meridian.
	West on true line between secs. 24 and 25.