

## Subdivisions of T. 1 N., R. 30 E.

Chains		
11.24	To top of ascent.	
20.24	Commence descend.	+15
40.12	Set a post for quarter section cor. and raised mound of Earth and drove a charred stake as per instructions.	-25
80.24	The corner to secs. 23, 24, 25 and 26. Land, considerably rolling. Soil, good, 2nd rate.	
	North between secs. 23 and 24. Commence to descend from post.	
40.00	Set quarter sec. post and raised mound of Earth with pits and trench, drove charred stake as per instructions.	-50
80.00	Set post for corner to secs. 13, 14, 23 and 24. Drove charred stake, raised mound of stone as per instructions. Land, rolling Prairie. Soil, good, 2nd rate.	Level
	East on random line between secs. 13 and 24. Var. 21° 30' E.	
40.00	Set temporary quarter sec. post on top of hill.	+50
80.48	Intersect Guide Meridian corner to secs. 13, 18, 19, and 24, 38 lks. South of corner to secs. 13 and 24, 18 and 19. S. 89° 44' W. on true line between secs. 13 and 24.	-150
37.48	To top of ascent.	+150
40.24	Set quarter sec. post and descend; drove a charred stake and raised mound as per instructions.	
80.48	The corner to secs. 13, 14, 23 and 24. Land, rolling Prairie. Soil, good, 2nd rate.	
	North between secs. 13 and 14. Commence to ascend gently from post.	
2.00	Commence gentle descent.	-15
40.00	Set quarter sec. post and raised mound of Earth and drove charred stake with pits and trench as per instructions.	-25