

Subdivisions of T. 1 N., R. 30 E.

Chains	S. 89° 42' W., on true line between secs. 1 and 12.	
40.21	Set post for quarter section corner, drove charred stake and raised mound of earth with trench and pits as per instructions.	
80.42	The post corner to secs. 1, 2, 11 and 12. Land, rolling prairie. Soil, good, 2nd rate.	
	October 30, 1860.	
	North on random line between secs. 1 and 2.	
40.00	Set temporary quarter sec. post.	-40
81.75	Intersect North boundary of Township, 68 lks. West of post corner to secs. 1 and 2.	-80
	S.0° 29' W., on true line between secs. 1 and 2. Commence to ascend.	
41.75	Set quarter sec. post; drove charred stake and raised mound of earth with trench and pits as per instructions, and ascend.	+40
66.75	To top of ascent.	+80
76.75	Commence to descend.	
81.75	The corner to secs. 1, 2, 11 and 12. Land, rolling prairie. Soil, same as last mile.	-25
	North between secs. 34 and 35.	
40.00	Set quarter sec. post, drove charred stake and raised mound of earth with trench and pits as per instructions.	
80.00	Set post on side hill, corner to secs. 26, 27, 34 and 35. Drove charred stake and raised mound of earth with trench and pits as per instructions. This line crosses several ridges and hollows running into big hollow, before noted. Land and soil same as last mile.	
	East on random line between secs. 26 and 35. Var. 18° 45' E.	