

Subdivisions of T. 1 N., R. 30 E.

Chains		
40.21	Set a post for quarter sec. corner, drove charred stake and raised mound of earth with trench and pits as per instructions.	
80.42	The post corner to secs. 9, 10, 15 and 16. Land, nearly level, gentle descent to the North. Soil, 2nd rate.	
	North between secs. 9 and 10.	
40.00	Set a post for quarter sec. corner, drove charred stake and raised mound of earth with trench and pits as per instructions.	
80.00	Set a post for corner to secs. 3, 4, 9 and 10. Drove charred stake and raised mound of earth with trench and pits as per instructions. Land, gently rolling. Soil, good, 2nd rate.	
	East on random line between secs. 3 and 10. Var. 20° 30' E.	
40.00	Set temporary quarter sec. post.	-40
80.56	Intersect corner to secs. 2, 3, 10 and 11 at post. West on true line between secs. 3 and 10.	-100
40.28	Set a post for quarter sec. corner, drove charred stake and raised mound of earth as per instructions.	+40
61.56	Top of Butte and descend.	+50
71.56	To foot of Butte.	-50
80.56	The corner to secs. 3, 4, 9 and 10. Land, broken and stony. Soil, 2nd and 3rd rate.	
	North on random line between secs. 3 and 4.	
40.00	Set temporary quarter sec. post.	-100
82.00	Intersect North boundary of Township, 12 lks. West of corner to secs. 3 and 4. S.00° 05' W. on true line between secs. 3 and 4.	-50
42.00	Set a post for quarter sec. cor, drove charred stake and	+50