

## Subdivisions of T. 1 N., R. 30 E.

Chains	raised mound of earth with trench and pits as per instructions.	
65.25	To top of rocky point and descend.	+100
82.00	The post corner to secs. 3, 4, 9 and 10. Land, rolling prairie. Soil, good, 2nd rate.	
40.00	North between secs. 32 and 33. Set a post for quarter sec. corner, drove charred stake and raised a mound of earth with trench and pits as per instructions.	
80.00	Set a post for corner to secs. 28, 29, 32 and 33. Drove charred stake and raised mound of earth with trench and pits as per instructions. Land, nearly level prairie, a little rolling. Soil, good, 2nd rate.	
40.00	East on random line between secs. 28 and 33. Var. $19\frac{1}{2}^{\circ}$ E. Set temporary quarter sec. post on ridge.	+40
80.46	Intersect corner to secs. 27, 28, 33 and 34 at post. West on true line between secs. 28 and 33.	
40.23	Set a post for quarter section corner, drove charred stake and raised mound of earth with trench and pits as per instructions.	
80.46	The corner to secs. 28, 29, 32 and 33. This line runs over rolling prairie descending N. towards big hollow, before noted. Soil, good, 2nd rate. November 2, 1860	
40.00	North between secs. 28 and 29. Set quarter sec. post, drove charred stake and raised mound of earth with trench and pits as per instructions.	Level
80.00	Set a post for corner to secs. 20, 21, 28 and 29 and	