

## Subdivisions of T. 1 N., R. 30 E.

Chains		
	<p>drove charred stake and raised mound of earth with trench and pits as per instructions. This line crosses several small ridges and hollows running N.E. into big hollow before noted.</p> <p>Land, rolling prairie.</p> <p>Soil, good, 2nd rate.</p>	
<p>40.00</p> <p>80.00</p> <p>11.00</p> <p>40.00</p> <p>42.00</p> <p>63.00</p> <p>80.00</p>	<p>East on a random line between secs. 21 and 28.</p> <p style="text-align: center;">Var. 19° E.</p> <p>Set temporary qr. sec. post and descend.</p> <p>Intersect N. and S. line, 16 lks. South of corner to secs. 21, 22, 27 and 28.</p> <p>S. 89° 53' W., on true line between secs. 21 and 28.</p> <p>To hollow and ascend.</p> <p>Set quarter sec. post, drove charred stake and raised mound of earth with trench and pits as per instructions.</p> <p>To summit and descend.</p> <p>Cross hollow and ascend.</p> <p>The corner to secs. 20, 21, 28 and 29.</p> <p>Land, rolling prairie.</p> <p>Soil, 2nd rate.</p>	<p>Level</p> <p>†50</p>
<p>40.00</p> <p>80.00</p>	<p>North between secs. 20 and 21.</p> <p>Set a post for quarter section corner, drove charred stake and raised mound of earth with trench and pits as per instructions.</p> <p>Set a post for corner to secs. 16, 17, 20 and 21. Drove a charred stake and raised mound of earth as per instructions.</p> <p>Land, gently rolling prairie.</p> <p>Soil, good, 2nd rate.</p>	
<p>40.00</p>	<p>East on a random line between secs. 16 and 21.</p> <p style="text-align: center;">Var. 19° 55' E.</p> <p>Commence descend from post.</p> <p>Set temporary quarter sec. post.</p>	<p>†100</p>