

Subdivisions of T. 1 N., R. 30 E.

Chains		
40.00	Set a post for quarter sec. corner, drove charred stake and raised mound with trench and pits as per instructions.	
45.00	To top of ascent.	+50
50.00	Commence to descend.	
70.00	To foot of descent.	-100
71.75	To Indian Trail, course N.W. and S.E.	
79.00	Cross big hollow and ascend rocky bluff.	
80.00	Set a post for corner to secs. 5, 6, 7 and 8. Drove charred stake and raised mound of stone as per instructions.	+25
	Land, rolling prairie except last chain.	
	Soil, 2nd rate.	
	East on a random line between secs. 5 and 8.	
	Var. 18° E.	
40.00	Set temporary qr. sec. post.	-25
80.32	Intersect N. and S. line, 48 lks. North of corner to secs. 4, 5, 8 and 9.	
	N. 89° 39' W. on a true line between secs. 5 and 8.	
2.32	Commence to descend.	
30.57	To foot of descent and ascend.	-100
40.16	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound of earth as per instructions.	+50
45.32	To top of ascent and descend.	+100
62.32	To foot of descent and ascend.	-50
67.82	To top of ascent and descend.	+75
80.32	The post corner to secs. 5, 6, 7 and 8.	
	Land, broken in places, balance rolling.	
	Soil, 2nd and 3rd rate.	
	West on a random line between secs. 6 and 7.	
40.00	Set temporary quarter sec. post.	+25
86.50	Intersect West boundary of Township at post corner to secs. 6 and 7.	Level