

## Subdivisions of T. 1 N., R. 30 E.

Chains	East on a true line between secs. 6 and 7.	
46.50	Set a post for quarter sec. corner, drove a charred stake and raised mound of earth as per instructions.	
55.00	To foot of descent.	-25
70.00	To a Trail, course S.E. and N.W.	
84.50	Commence to ascend.	
86.50	The corner to secs. 5, 6, 7 and 8. Land, gently rolling. Soil, good, 2nd rate.	
	North on a random line between secs. 5 and 6.	
40.00	Set temporary qr. sec. post on top of bluff.	+250
81.66	Intersect North boundary of Township, 45 lks. West of post, corner to secs. 5 and 6. S. 00° 19' W. on a true line between secs. 5 and 6.	
38.66	To top of gentle ascent.	
41.66	Set a post for quarter sec. corner, drove a charred stake and raised mound with trench as per instructions.	
81.66	The corner to secs. 5, 6, 7 and 8. Land, on bluff 2nd rate, balance good 2nd rate. Completed November 26, 1860.	-250
	General Description	
	This Township is of very good quality of land, generally well adapted to grazing purposes, very little wood. Some small willows were seen in a big hollow before noted; this runs through the Township from near the S.W. corner of sec. 36, generally in a N.W. direction and leaves the West boundary in the S.W. qr. of sec. 6 and is about 6 chains wide on an average. Three good springs of water were noticed in sec. 16. The land is rolling, generally level in places along the S. boundary. Soil, good, 2nd rate, generally a little 3rd rate.	