

Subdivisions of T. 1 N., R. 31 E.

Chains	
39.82	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
79.65	The corner to secs. 13, 14, 23 and 24. Land, rolling grass hills. Soil, 2nd rate.
	North between secs. 13 and 14.
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.00	Set a post for corner to secs. 11, 12, 13 and 14, drove charred stake and raised mound with trench as per instructions. Land, rolling grass hills. Soil, 2nd rate.
	East on random line between secs. 12 and 13. Var. 20° 00' E.
40.00	Set a post for $\frac{1}{4}$ sec. cor.
79.84	Intersected East boundary of Township, 20 lks. South of corner to secs. 12 and 13, from which corner I run. S. 89° 51' W., on true line between secs. 12 and 13.
39.92	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
79.84	The corner to secs. 11, 12, 13 and 14. Land, rolling grass hills. Soil, 2nd rate.
	North between secs. 11 and 12.
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
65.00	Entered small valley bearing N.E. and S.W.
78.00	Leave valley bearing N.E. and S.W.
80.00	Set a post for corner to secs. 1, 2, 11 and 12, raised stone mound as per instructions.
	East on random line between secs. 1 and 12.