

Subdivisions of T. 1 N., R. 31 E.

Chains	
	Var. 20° 00' E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
79.18	Intersected East boundary of Township, 30 lks. South of the corner to secs. 1 and 12 from which corner I run. S. 89° 47' W. on true line between secs. 1 and 12.
39.59	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instruction.
68.00	Enter small valley bearing N. and S.W. from which point a beautiful fresh water spring bears North about 20.00 chs. dist.
78.00	Leave Valley bearing N. and S.W.
79.18	The corner to secs. 1, 2, 11 and 12. Land, Valley 1st rate soil, East of valley gently rolling, 2nd rate soil.
	October 17th, 1860.
	North on random line between secs. 1 and 2.
40.00	Set a temporary $\frac{1}{4}$ sec. cor.
80.90	Intersect North boundary of Township, 70 links East of the corner to secs. 1 and 2 from which corner I run. S. 00° 30' E. on true line between secs. 1 and 2.
40.90	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
44.90	To a dry Ravine, course East.
80.90	The corner to secs. 1, 2, 11 and 12. Land, rolling grass hills. Soil, light 2nd rate.
	North between secs. 34 and 35.
32.00	To a dry Ravine, course N.E.
40.00	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.00	Set post for corner to secs. 26, 27, 34 and 35, drove charred stake and raised mound with trench as per instructions. Land, rolling grass hills.