

## Subdivisions of T. 1 N., R. 31 E.

Chains	N. 89° 57' W. on true line between secs. 11 and 14.
39.96	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
44.40	To a dry ravine, course North.
79.92	The corner to secs. 10, 11, 14 and 15. Land, rolling grass hills. Soil, 2nd rate.
	North between sec. 10 and 11.
32.00	To a dry ravine, course N.E.
40.00	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
41.00	Foot of hill bearing N.E. and S.W.
50.00	Sumit of hill bearing N.E. and S.W.
80.00	Set post for corner to secs. 2, 3, 10 and 11, drove charred stake and raised mound with trench as per instructions. Land, rolling grass hills. Soil, 2nd and 3rd rate.
	East on random line between secs. 2 and 11. Var. 19° 00' E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	I <sup>1</sup> ntersected N. and S. line, 16 lks. North of the corner to secs. 1, 2, 11 and 12 from which corner I run. N. 89° 53' W. on true line between secs. 2 and 11.
8.50	Top of ridge, bearing N. and S.
40.00	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.00	The corner to secs. 2, 3, 10 and 11. Land, rolling. Soil, 3rd rate.
	North on random line between secs. 2 and 3.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
81.84	Intersected North boundary of Township, 48 lks. East of