

Subdivisions of T. 1 N., R. 31 E.

Chains	
36.00	To a dry ravine, course N.E.
40.21	Set a post for $\frac{1}{2}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
71.43	To a dry ravine, course N.W.
80.43	The corner to secs. 15, 16, 21 and 22. Land, rolling grass hills. Soil, light 2nd rate.
	North between secs. 15 and 16.
40.00	Set a post for $\frac{1}{2}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.00	Set a post for corner to secs. 9, 10, 15 and 16, drove charred stake and raised mound with trench as per instructions. Land, level. Soil, good, 2nd rate.
	East on random line between secs. 10 and 15. Var. 20° 30' E.
40.00	Set temporary $\frac{1}{2}$ sec. cor.
80.03	Intersected N. and S. line, 21 lks. South of the corner to secs. 10, 11, 14 and 15, from which corner I run. S. 89° 51' W. on a true line between secs. 10 and 15.
40.01	Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.03	The corner to secs. 9, 10, 15 and 16. Land, gently rolling. Soil, 2nd rate. October 20th, 1860.
	North between secs. 9 and 10.
19.00	To a dry ravine, course N.E.
40.00	Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.
80.00	Set post for corner to secs. 3, 4, 9 and 10, drove charred stake and raised mound with trench as per