

Subdivisions of T. 1 N., R. 31 E.

Chains	<p>Soil, 3rd rate.</p> <p style="text-align: right;">October 22, 1860.</p>
<p>40.00</p> <p>80.00</p>	<p>North between secs. 31 and 32.</p> <p>Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.</p> <p>Set a post for corner to secs. 29, 30, 31 and 32, drove charred stake and raised mound with trench as per instructions.</p> <p>Land, gently rolling grass plains.</p> <p>Soil, 2nd rate.</p>
<p>40.00</p> <p>79.91</p> <p>39.95</p> <p>79.91</p>	<p>East on random line between secs. 29 and 32.</p> <p style="text-align: right;">Var. 20° 00' E.</p> <p>Set temporary $\frac{1}{4}$ sec. cor.</p> <p>Intersected N. and S. line, 19 lks. North of the corner to secs. 28, 29, 32 and 33, from which corner I run. N. 89° 52' W. on true line between secs. 29 and 32.</p> <p>Set post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instructions.</p> <p>The corner to secs. 29, 30, 31 and 32.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
<p>40.00</p> <p>89.36</p> <p>49.36</p> <p>89.36</p>	<p>West on random line between secs. 30 and 31.</p> <p>Set temporary $\frac{1}{4}$ sec. cor.</p> <p>Intersect West boundary of Township, 50 lks. South of the corner to secs. 30 and 31, from which corner I run. S. 89° 39' E. on true line between secs. 30 and 31.</p> <p>Set a post for $\frac{1}{4}$ sec. cor., drove charred stake and raised mound with trench as per instruction.</p> <p>The corner to secs. 29, 30, 31 and 32.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>