

Base Line through Range 32 East.  
 Surveyed by David P. Thompson under contract No. 79.  
 Dated July 26, 1858.

Chains	187th Mile East on South boundary of sec. 31. Var. 20° East.
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of earth &c as per instructions.
80.00	Set a stone, 10 x 10 x 18, for corner to secs. 31 and 32 and build a mound of earth as per instructions. Land, level grass plain.
	188th Mile East on South boundary of sec. 32. Var. 20° East.
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of earth as per instructions.
80.00	Set a stone, 12 x 8 x 15 ins., for corner to secs. 32 and 33 and build a mound of earth as per instructions. Land, gently rolling grass hills. Soil, 2nd rate. June 7th, 1859.
X	189th Mile East on South boundary of sec. 33. Var. 19° 40' East.
40.00	Set a stone, 15 x 12 x 15 ins., for $\frac{1}{4}$ sec. corner and build a mound of earth as per instructions
60.75	McKays Creek, 50 lks. wide, runs North.
80.00	Set post for corner to secs. 33 and 34 and build a mound of earth as per instructions. Land, level bottom. Soil, 1st rate. Cotton Wood timber on banks of creek.
	190th Mile East on South boundary of sec. 34. Var. 20° 45' East.
40.00	Set post for $\frac{1}{4}$ sec. corner and build a mound of earth &c as per instructions.