

## Exterior Boundaries of T. 1 N., R. 32 E.

| Chains |   |
|--------|---|
|        | <p>Land, gently rolling.<br/>Soil, 1st rate.</p>  |
|        | <p>West on South boundary of sec. 31.<br/>Var. 20° East.</p>  |
| 7.00   | Old established corner to secs. 31 and 32.  |
| 40.00  | Set stone, 15 x 8 x 8 ins., for $\frac{1}{4}$ sec. corner.  |
| 47.70  | Old $\frac{1}{4}$ sec. corner.  |
| 88.10  | <p>To established corner to Township 1 North, Ranges 31 and 32 East on base line.<br/>I find the error to be 8.10 chs. in six miles and that the intersection on North boundary is correct.</p> |
|        | <p>I then commence at the N.W. corner and run.<br/>S. 89° 55' East on North boundary of sec. 6.<br/>Var. 20° East.</p>  |
| 48.90  | Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.   |
| 88.90  | <p>Set post for corner to secs. 5, 6, 31 and 32 in mound of earth with charred stake, pits, trench &amp;c as per instructions.</p>  |
|        | <p>Land, gently rolling.<br/>Soil, good 2nd rate.</p>   |
|        | <p>S. 89° 55' East on North boundary of sec. 5 .<br/>Var. 20° East.</p>   |
| 40.00  | Set stone, 24 x 14 x 5 ins., for $\frac{1}{4}$ sec. corner.   |
| 80.00  | <p>Set post for corner to secs. 4, 5, 32 and 33 in mound of earth with charred stake, pits, trench &amp;c as per instructions.</p>  |
|        | <p>Land, gently rolling.<br/>Soil, good, 2nd rate.</p>  |
|        | <p>S. 89° 55' East on North boundary of sec. 4.<br/>Var. 20° East.</p>  |
| 39.62  | Birch Creek (dry), course North.  |