

## Exterior Boundaries of T. 1 N., R. 32 E.

Chains	Var. 19° 30' East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits, trench &c as per instructions.
80.00	The established corner to Townships 1 and 2 North, Ranges 32 and 33 East. Land, level. Soil, 1st rate.  September 9th, 1864.
General Description	
The quality of the land in this Township is generally 1st rate level or gently rolling and is well watered with numerous springs and streams flowing through it. There is but little timber and what there is is of very poor quality and of but little value except for fuel. There are a large number of settlers in this Township and a large amount of grain and hay has been produced this season. This Township should be subdivided.	
Subdivisions of T. 1 N., R. 32 E. Surveyed by Daniel Chaplin under contract No.107. Dated September 21, 1864.	
North between secs. 35 and 36.	
40.00	Set stone, 17 x 10 x 8, for $\frac{1}{4}$ sec. corner.
80.00	Set post for corner to secs. 25, 26, 35 and 36 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 1st rate.
East on a random line between secs. 25 and 36.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect East boundary at corner to secs. 25 and 36 from which corner I run. West on a true line between secs. 25 and 36.
40.00	Set stone, 18 x 10 x 10, for $\frac{1}{4}$ sec. corner.