

## Subdivisions of T. 1 N., R. 32 E.

Chains 80.00	Intersect N. and S. line at corner to secs. 11, 12, 13 and 14 from which I run. West on a true line between secs. 11 and 14.
36.50	Dry bed of creek runs N. 10° W.
40.00	Set post for $\frac{1}{4}$ sec. cor., from which A balm, 18 ins. diam., bears S. 75° E. 95 lks. dist. " " 18 " " " N. 57° E. 100 " "
80.00	The corner to secs. 10, 11, 14 and 15. Land, rolling. Soil, good, 2nd rate. Some balm timber on dry creek.
	North between secs. 10 and 11. Var. $19\frac{1}{2}^{\circ}$ E.
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	Set stone, 20 x 16 x 8, for corner to secs. 2, 3, 10 and 11. Land, level. Soil, 1st rate.
	East on a random line between secs. 2 and 11.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. and S. line at corner to secs. 1, 2, 11 and 12 from which I run. West on a true line between secs. 2 and 11.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
70.30	Brook, 6 lks. wide runs North.
80.00	The corner to secs. 2, 3, 10 and 11. Land, rolling. Soil, 2nd rate.
	North on a random line between secs. 2 and 3. Var. $19\frac{1}{2}^{\circ}$ East.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.