

Subdivisions of T. 1 N., R. 32 E.

Chains	East on a random line between secs. 15 and 22.	
40.00	Set temporary $\frac{1}{4}$ sec. corner.	
80.00	Intersect N. and S. line at corner to secs. 14, 15, 22 and 23 from which corner I run.	
	West on a true line between secs. 15 and 22.	
20.10	Enter field, bears N. and S.	
37.10	Dry bed of Birch creek, course North.	
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, with pits &c as per instructions.	
42.25	Leave field, bears N. and S.	
80.00	The corner to secs. 15, 16, 21 and 22.	†200
	Land, rolling.	
	Soil, 1st rate.	
	Cotton wood timber on the creek banks.	
	October 21st, 1864.	
	North between secs. 15 and 16.	
	Var. 20° E.	
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.	
80.00	Set post for corner to secs. 9, 10, 15 and 16 in mound of earth with charred stake, pits &c as per instructions.	
	Land, gently rolling.	
	Soil, 2nd rate.	
	East on a random line between secs. 10 and 15.	
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.	
79.76	Intersect N. and S. line, 68 lks. North of corner to secs. 10, 11, 14 and 15 from which I run.	
	N. 89° 31' W. on a true line between secs. 10 and 15.	
18.90	Road bears N. and S.	
39.88	Set stone, 16 x 10 x 8, for $\frac{1}{4}$ sec. corner. Descend hill.	
55.00	Foot of hill.	
57.00	Birch Creek, 10 lks. wide, runs N.W.	
77.25	Road bears N.W. and S.E.	
79.76	The corner to secs. 9, 10, 15 and 16.	