

Subdivisions of T. 1 N., R. 32 E.

Chains 80.00	Set post for corner to secs. 8, 9, 16 and 17 in mound of earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, good, 2nd rate.
	East on a random line between secs. 9 and 16.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.00	Intersect N. and S. line at corner to secs. 9, 10, 15 and 16 from which I run. West on a true line between secs. 9 and 16.
40.00	Set post for $\frac{3}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
80.00	The corner to secs. 8, 9, 16 and 17. Land, rolling. Soil, good, 2nd rate.
	North between secs. 8 and 9. Var. $19\frac{1}{2}^{\circ}$ E.
40.00	Set stone, 15 x 8 x 6, for $\frac{1}{4}$ sec. corner.
80.00	Set stone, 22 x 15 x 4, for corner to secs. 4, 5, 8 and 9. Land, rolling. Soil, 2nd rate.
	East on a random line between secs. 4 and 9.
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
80.00	Intersect N. and S. line at corner to secs. 3, 4, 9 and 10 from which corner I run. West on a true line between secs. 4 and 9.
1.00	Birch Creek, 10 lks. wide, runs N.E.
14.00	Road bears N. and S.
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	The corner to secs. 4, 5, 8 and 9. Land, rolling. Soil, 1st rate