

## Subdivisions of T. 1 N., R. 32 E.

Chains	
	North between secs. 19 and 20. <div style="text-align: center;">Var. 20° E.</div>
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	Set stone, 18 x 12 x 8, for corner to secs. 17, 18, 19 and 20.
	Land, gently rolling.
	Soil, 2nd rate.
	East on a random line between secs. 17 and 20.
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.
80.00	Intersect N. and S. line, 70 lks. North of corner to secs. 16, 17, 20 and 21 from which I run,
	N. 89° 30' W. on a true line between secs. 17 and 20.
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	The corner to secs. 17, 18, 19 and 20.
	Land, rolling.
	Soil, 2nd rate.
	West on a random line between secs. 18 and 19.
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
88.34	Intersect West boundary, 80 lks. South of corner to secs. 18 and 19 from which corner I run,
	S. 89° 26' E. on a true line between secs. 18 and 19.
48.34	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
88.34	The corner to secs. 17, 18, 19 and 20.
	Land, hilly.
	Soil, 2nd rate.
	North between secs. 17 and 18.
	<div style="text-align: center;">Var. 20 <math>\frac{3}{4}</math>° East.</div>
40.00	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to secs. 7, 8, 17 and 18 in mound of