

Subdivisions of T. 1 N., R. 32 E.

Chains	<p>earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, 2nd rate.</p>
40.00	East on a random line between secs. 8 and 17.
79.80	<p>Set post for temporary $\frac{1}{4}$ sec. cor. Intersect N. and S. line at corner to secs. 8, 9, 16 and 17 from which corner I run,</p>
39.90	West on a true line between secs. 8 and 17.
79.80	<p>Set stone, 18 x 8 x 8, for $\frac{1}{4}$ sec. cor. The corner to secs. 7, 8, 17 and 18. Land, gently rolling. Soil, 2nd rate.</p>
40.00	West on a random line between secs. 7 and 18.
88.40	<p>Set post for temporary $\frac{1}{4}$ sec. corner. Intersect West boundary, 75 lks. South of corner to secs. 7 and 18 from which corner I run,</p>
48.40	S. $89^{\circ} 28'$ E. on a true line between secs. 7 and 18.
88.40	<p>Set stone, 18 x 7 x 9, for $\frac{1}{4}$ sec. cor. The corner to secs. 7, 8, 17 and 18. Land, rolling. Soil, 2nd rate.</p>
40.00	<p>North between secs. 7 and 8. Var. 20° E. Set post for $\frac{1}{4}$ sec. corner in mound of earth, with charred stake, pits &c as per instructions.</p>
80.00	<p>Set post for corner to secs. 5, 6, 7 and 8 in mound of earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, good, 2nd rate.</p>
40.00	East on a random line between secs. 5 and 8.
79.78	<p>Set post for temporary $\frac{1}{4}$ sec. cor. Intersect N. and S. line at corner to secs. 4, 5, 8 and 9.</p>