

Subdivisions of T. 1 N., R. 32 E.

Chains	West between secs. 10 and 15.
18.00	To boundary of Indian Reservation.
	South between secs. 14 and 15.
37.00	To boundary of Indian Reservation.
	Land, rolling.
	Soil, good.
	North between secs. 10 and 11.
	Var. 20° E.
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
80.00	Set stone, 18 x 16 x 10, for cor. to secs. 10, 11, 2 and 3.
	Land, level.
	Soil, good.
	East on random between secs. 2 and 11.
	Var. 20° E.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.12	Intersected N. and S. line at corner.
	W. on true line.
40.06	Set stone, 18 x 14 x 7, for $\frac{1}{4}$ sec. cor.
55.00	Enter Indian field.
59.00	Leave field.
72.00	To Howetome creek, N.
80.12	To corner.
	Land, rolling.
	Soil, 2nd rate.
	West between secs. 3 and 10.
5.50	Leave bottom.
40.00	Set post and made earth mound for $\frac{1}{4}$ sec. cor.
45.00	To boundary of Indian Reservation.
	North on random between secs. 2 and 3.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.50	Intersected North bdy. at cor.