

T. 1 N., R. 32 E.

Chains	
40.00	<p>West on North boundary of sec. 2.</p> <p style="text-align: center;">Var. 20° E.</p> <p>Set post and made earth mound for $\frac{3}{4}$ sec. cor.</p>
80.00	<p>Set stone, 18 x 14 x 12, for cor. to sec. 2, 3, 34 and 35.</p> <p>Land, rolling. Soil, good.</p>
25.40	<p>West on North boundary of sec. 3.</p> <p style="text-align: center;">Var. 21° E.</p> <p>Howetome creek, dry bed, course N.</p>
27.10	<p>Leave creek bottom.</p>
40.00	<p>Set post and made earth mound for $\frac{1}{4}$ sec. cor.</p>
74.00	<p>To the boundary of the Reservation.</p> <p>Land, generally rolling.</p> <p>Soil, good. Grass, good.</p>
1.50	<p>West on North boundary of sec. 4.</p> <p style="text-align: center;">Var. 20° 30' E.</p> <p>Old Wagon road, N. and S.</p>
12.50	<p>To boundary line of Reservation.</p> <p>Land, rolling.</p> <p>Soil, good. Grass, good.</p> <p style="text-align: right;">November 3, 1871.</p>
	<p>Base Line through T. 1 N., R. 32 E. Surveyed by James P. Currin & James E. Noland, special contract Dated May 4, 1887.</p>
	<p>Beginning at the cor. to secs. 34 and 35, T. 1 N., R. 32 E. on base line which is a post 4 ft. long, 4 ins. square, set firmly in the ground around which is a mound of stone. The mound of earth and pits have been destroyed and the post is badly decayed. Marks on it being mostly illegible. But it is affirmed by old settlers to be in the exact place of the original location of cor. Remark cor. and repaired the mound of stone. Thence I run due East on random on S. boundary of secs.</p>