

Base Line through T. 1 N., R. 32 E.

Chains		
	<p>35 and 36. Var. 20° East.</p> <p>Set temporary sec. and $\frac{1}{4}$ sec. cors. at proper distances and at 2 miles intersect N. and S. line at cor. to Tps. 1 N., Rgs. 32 and 33 E.</p> <p>This cor. has been nearly destroyed, only old pits and mound remaining to be seen.</p> <p>After re-establishing this cor. by setting a basalt stone, 16 x 14 x 10 ins., 11 ins. in the ground for standard cor. to Tp. 1 N., Rgs. 32 and 33 E. marked S C with 6 notches on N, E and W. edges and raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it.</p> <p>Thence West on true line on S. boundary sec. 36.</p> <p style="text-align: center;">Var. 20° East.</p>	
18.70	Closing cor. to Tps. 1 S., Rgs. 32 and 33 E. which is a marked stone (x) in mound of stone.	
19.15	Dry gulch, course N.W.	
40.00	Set basalt stone, 12 x 8 x 7 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ S C on N. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
40.50	Ravine, course S.	20
57.60	Summit of ridge bears N.W.	100
74.75	Trail bears N.E. and S.W.	
78.00	Bluff rock.	25
79.00	Creek bottom.	
80.00	<p>Set basalt stone or boulder, 16 x 12 x 6 ins., 10 ins. in the ground for cor. to secs. 35 and 36, T. 1 N., R. 32 E. marked S C with 1 notch on E. and 5 notches on W. edges, dug pits, 18 x 18 x 12 ins. N., E and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it from which</p> <p style="text-align: center;">A balm, 15 ins. diam., bears N. 50° W., 61 lks. dist.</p> <p style="text-align: center;">marked S C S 35, T 1 N R 32 B T.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p> <p>Grass, good.</p>	